OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 3rd July 1939.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2 P.M. on 24th July 1939, for constructing the western extensions of Exhibition Buildings, Mysore.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of rupee one for each form, should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing western extensions of Exhibition Buildings, Mysore." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 3,528 only in cash or Government Security, Municipal Debentures, Post Office Cash Certificates (at cash payment value at the time of deposits and not face value), as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest.) In case of the acceptance of the tender, an addition of five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department Form. The amount of earnest money should be paid direct to treasury and the duplicate treasury challan submitted separately along with the tender.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 24th July 1939 at 4 P.M. The final acceptance of the tender will rest with the Government who do not bind themselves to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions or additions, at the discretion of the Assistant Engineer or his representative. The tendered rates will hold good for any quantity whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the end of December 1939, failing which the Assistant Engineer may, at his discretion, levy a penalty up to Rs. 50 per day of delay which will be recovered from the contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally, binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the Assistant Engineer in the interest of the work, shall be accepted by the tenderer at the rates fixed by the Assistant Engineer and the tenderer will pay the hire, etc., on machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water-shoots, coverings to masonry, tile pieces to steps, sieves, parahs, or measures, shoring and other requisite protection during the progress of the work.
(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.
(10) Afford facilities to any other parties employed upon the work so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(*b*) It is the business of the contractors to make their own arrangements for quarries and supplies of materials.

23. The rates for woodwork for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 14,000 will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore teak is as follows:—

	Rs.	a.	p.	
(1) Selected 1st class logs	2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″	3	4	0	„
(2*a*) Do 3″×5″ to 4″×7″	3	12	0	„
(3) Planks 1″ to 1¼″ to required sizes	4	8	0	„

25. Only Chamundi Brand cement should be used for all works requiring this nature.

26. Such of the tenders which do not clearly quote with detailed specifications for all the items without exception will not be considered.

Abstract quantities of estimate for extending the Western Wing of Exhibition Buildings, Mysore.

Item No.	Description of work	Unit	Rate	Contents
			Rs. a. p.	
	GROUND FLOOR:			
1	Earthwork excavation for foundations and filling in basement with watering and consolidating	C.yd.		751
2	Burnt stone jelly concrete 1 : 2 : 4 in lime mortar with tamping in layes of not more than 6 inches thick	C.ft.		5,814
3	Burnt size stone in lime mortar for foundations, with bond stones 6 ft. apart	C.ft.		9,132
4	Burnt size stone in lime mortar for basement with bond stones 6 ft. apart with all quoins neatly dressed, 2 inches wide	C.ft.		2,836
5	Burnt stone slabs 6″ thick for basement and steps including two lines dressing on exposed faces and one line dressing on all other faces	S.ft.		1,325
6	Wirecut brick in cement mortar including bond slabs of cement concrete at every 4 ft. intervals for superstructure	C.ft.		10,158
7	R.C.C. lintels with sufficient reinforcement with plastering, etc., complete	C.ft.		341
8	Cement concrete slabs 1 : 2 : 4 for sills of windows, bed plates below girders and roof	C.ft.		585
	(*a*) Exhaust fans in ventilators as per design	Each		40
9	R.C.C. perporated ventilators as per design	S. ft.		72
10	Burnt brick in mud	C.ft.		380

Item No.	Description of work	Unit	Rate	Contents
			Rs. a. p.	
11	R.C.C. pillars 1 : 2 : 4 with sufficient reinforcement with plastering, etc., complete	C.ft.		256
12	Burnt stone slabs 6″ thick one line dressed for the lintel of windows in temporary walls of stalls	Sq.ft.		48
13	Plastering with chunam mortar smooth	Sqr.		190·85
14	White and colour washing, two coats	Sqr.		190·85
15	Wirecut brick in cement mortar archwork	C.ft.		106
16	Pointing the basement with cement and lining nicely ..	Sqr.		10·50
17	Rolled steel girders as per B.S.S. including, lifting, hoisting and boxing with cement mortar and terrace brick, reinforced galvanized steel tex tied from above alround, with one coat of anticorrosive paint and fixing with cement concrete in walls	Cwt.		213
18	Teakwood doors with frames 3″×5″ without bottom sills having $\frac{1}{3}$ panelled and $\frac{2}{3}$ glazed (pilkington's pin headed $\frac{1}{8}$″) $1\frac{1}{2}$″ thick shutters including Acme brass fittings, rimdoor locks with handles, 3 finger plates 12″×4″ as per design with six inch brass hinges, 2 six inches hooks, brass screws, barrel bolts of suitable size, etc., with ventilator above including two coats of Dulex Varnish	Sq. ft.		359
19	Collapsible steel shutters with required varnish, two coats ..	Sq. ft.		154
20	Teakwood windows 3″×5″ frame with $1\frac{1}{4}$″ thick glazed shutters opening out side in four halves with ventilators at top including iron bars $\frac{3}{4}$″ diameter 4″ apart, brass hinges, hooks, 2″ rings and easement adjusting, stays, etc., complete, including two coats of Dulex Varnish	Sq. ft.		727
21	Show windows with plate glass $\frac{1}{4}$″ thick in the stall with required brass fittings including two coats of Dulex Varnish ..	Sq.ft.		1,078
22	Food lifts with required arrangements	Each		2
23	Roofing with R.B.C. as per specification in force including plastering both sides	Sqr.		33·85
24	Roofing with reinforced cement concrete terrace 1: 2 : 4 with sufficient reinforcement to take a super load of 120 lbs. per sq.ft. with bottom ceiling plastered with nicely ground chunam mortar both sides	Sqr.		24·25
25	Providing R.C.C. chajja 3″ average thick 5′ wide with anchorage of $1\frac{1}{8}$′ into the wall with plastering, etc., complete ..	S.ft.		1,500
26	Skirting to the walls with cement concrete $\frac{1}{2}$″ thick 1 : 2 : 4 with topping of coloured cement $\frac{1}{4}$″ thick, 9″ high as per design	R.ft.		900
27	Flooring with cement concrete $1\frac{1}{2}$″ thick over a bed of 4″ thick lime concrete with topping of red cement $\frac{1}{4}$″ thick finished with ironite $2\frac{1}{2}$ lbs. per square and cut to the required tile pattern where required with all corners rounded	Sqr.		36.50
28	Flooring with milk white glazed tiles on a bed of 4″ thick lime concrete and the joints pointed with white cement ..	Sqr.		17.00
29	Burnt brick in cement mortar. partition wall with brick on edge 3″ thick including reinforcement $1\frac{1}{2}$ per cent in every third course with plastering and white washing, etc., complete	S.ft.		1,327
30	Providing and fixing R.C.C. cantilever stair 4′-6″ wide with 14″ tread and 6″ rise surface finished with ironite and rendered non-slip including teakwood hand railing with two horizontal pipes of $1\frac{3}{4}$″ dia. with two coats of required varnish.	"Visible tread area" S.ft.		387

Abstract estimate of quantities for extending the Western Wing of Exhibition Buildings, Mysore.

	FIRST FLOOR.			
1	Burnt brick in lime mortar including bond slabs of cement concrete at every 4 ft. intervals for superstructure ..	C.ft.		10,170
2	R.C.C. slabs with sufficient reinforcement with plastering, etc., complete	C.ft.		220
3	Cement concrete slabs 1 : 2 : 4 for sills of windows and bed plate of below girders and roof	C.ft.		533

Item No.	Description of work	Unit	Rate	Contents
			Rs. a. p.	
4	R.C.C. perforated ventilators as per design	S.ft.		63
	(a) Exhaust fans in alternative ventilators	Each		32
5	Burnt brick in mud	C.ft.		583
6	Burnt stone slabs 6″ thick, one line dressed for the lentel of windows in temporary walls of stalls	S.ft.		48
7	R.C.C. pillars 1 : 2 : 4 with sufficient reinforcement with plastering, etc., complete	C.ft.		256
8	Plastering with chunam mortar	Sqr.		200.64
9	White and colour washing, two coats	Sqr.		200.64
10	Rolled steel girders as per B.S.S. including lifting and hoisting and boxing with cement mortar and terrace bricks reinforced with galvanized steel tox tied alround with one soat of anticorrosive painting and fixing with cement concrete in walls	Cwt.		208
11	Teakwood doors with frames 3″×5″ without bottom sills, having $\frac{1}{3}$ panelled, $\frac{2}{3}$ glazed (pilkington's pin headed $\frac{1}{8}$″) $1\frac{1}{2}$″ thick shutters including Acme brass fittings, rimdoor locks with handles, 3 finger plates 12″×4″ as per design with six inches brass hinges, 2 six inches hooks, brass screws, barrel bolts of suitable size, etc., with ventilators above including two coats of Dulex Varnish	S.ft.		248
12	Teakwood windows 3″@5″ frame with $1\frac{1}{4}$″ thick glazed shutters opening outside in four halves with ventilators at top, without iron bars, brass hinges, hooks, 2″ rings and easement adjusting stays, etc., complete including two coats of Dulex paint	S.ft.		1,260
13	Roofing with R.B.C. terrace as per specification in force including plastering both sides	Sqr.		33.85
14	Roofing with reinforced cement concrete terrace 1 : 2 : 4 with sufficient reinforcement to take a super load of 80 lbs. per Sq.ft. with 3″ thick surki concrete on top with two coats of flat tiles including plastering at top and bottom of ceiling with nicely ground lime mortar	Sqr.		28.01
15	Providing R.C. chejja 3″ average thick, 5′ wide with anchorage of $1\frac{1}{8}$′ into the wall with plastering, etc., complete	S.ft.		1,500
16	Skirting to the walls with cement concrete $\frac{1}{2}$″ thick 1 : 2 : 4 with topping of coloured cement $\frac{1}{4}$″ thick, 9″ high as per design.	R.ft.		900
17	Flooring with cement concrete $1\frac{1}{2}$″ thick with topping of red cement $\frac{1}{4}$″ thick finished with cronite $2\frac{1}{2}$″ lbs. per Sqr. and cut to the required tile pattern where required with all corners rounded	Sqr.		49.74
18	Burnt brick in cement mortar partition wall with brick on edge, 3″ thick including reinforcement $1\frac{1}{2}$ per cent in every third course with plastering and white washing, etc., complete	S.ft.		1,327
19	Balcony with R.C.C. as per design including plastering to the windows in front	Each		6
20	Burnt brick in lime mortar plain parapet wall 9″ thick, 2′ to $2\frac{1}{2}$′ high as per design including plastering and whitewashing, etc., complete	R.ft.		420
21	Rain water down pipes of cast iron 4″ dia. with bends, etc., complete	R.ft.		1,320
22	Flag staff with anchorage	Each		3

Abstract estimate of quantities for proposed Western Extension of Exhibition Buildings, Mysore.
Alternative items of works.

1	Filling in foundation with broken granite jelly in surki mortar	C.ft.		
2	Two line dressing to exposed faces of masonry	S.ft.		
3	Three lines dressing including fine palmane dressing	S.ft.		
4	Teakwood doors 3″×4″ frame with teakwood shutter and plain cement asbestos sheets including spring, hinges, etc., complete for bath rooms	S.ft.		
5	Reinforced cement concrete 1 : 2 : 4 of broken granite jelly for beams and lentels with reinforcement up to 5 per cent including beam plastering and moulding at bottom	C.ft.		

Item No.	Description of work	Unit	Rate	Contents
			Rs. a. p.	
6	Teakwood show windows with movable type of ventilators at top including fitting ¼″ plate glass supplied departmentally for ground floor only	S.ft.		
7	Providing and fixing ornamental C.I. ventilating grills for basement	S.ft.		
8	Ornamental coving with off sets as per design including plastering, etc., complete	R.ft.		
9	Partition wall with R.C.C. pillars 4″×4″ at intervals both horizontal and vertical including brick nogging with ordinary brick in cement including chunam plastering, etc., complete.	S.ft.		
10	Flooring with standard tiles including border of required design and cement pointing	Sqr.		
11	Milk white glazed dadoe tiles including convex and concave corners, etc., complete	Sqr.		
12	C.I. ornamental pillars of Bhadravati	Cwt.		

M. A. RAMANUJAM,
Assistant Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT GARDENS IN MYSORE, LAL-BAGH, BANGALORE.

Abstract Notification dated 30*th June* 1939.

The public are hereby informed that the last day for receiving quotations for the supply of fruit and other plants has been extended to Monday the 17th July 1939.

For detailed information attention is invited to detailed Notification published on pages 1138-1139, Part VI of the *Mysore Gazette*, dated 15th June 1939.

L. S. DORASAMI,
Superintendent.

MYSORE GOVERNMENT LIFE INSURANCE DEPARTMENT, BANGALORE.

Notification dated the 30*th June* 1939.

An old Remington Typewriter No. 11 (R. B. 12847), together with the totalling mechanism which was once part and parcel of it will be sold by auction on 24th July 1939 at 4-30 P.M. in the office premises.

The typewriter and its totalling mechanism may be seen by the intending bidders on working days between 11 A.M. and 5 P.M. Fifty per cent of the purchase price will have to be paid on the spot and the balance before removing the article from the premises.

The bid will start from Rs. 50.

G. MADHAVA RAO,
Deputy Secretary.

OFFICE OF THE DIRECTOR OF INDUSTRIES AND COMMERCE IN MYSORE, BANGALORE.

*Notification No. D.*1-123—37-38, *dated* 5*th July* 1939.

Attention of the public is invited to the notice published in the *Mysore Gazette*, dated 6th July 1939, part VI, page 1313, inviting applications for the post of Wool Weaving Instructor and Wool Dyeing Instructor in the Industrial School, Chitaldrug, on a pay of Rs. 35—3—50 according to qualifications.

M. S. RAMCHENDRA RAO,
Director.